

# Project Addendum No. 2

**Project:** New Entrance Feature for the  
Brownsville S.P.I. Int'l Airport  
COB Bid No. NEF-28-0410

**Addendum  
Date:** April 5, 2010

**From:** Vicente Mendez, PE

**Project No.:** 2995

**Reference:**

**Page(s):** Page 1 of 1

Urgent       For Review       Please Comment       Please Reply       Please Recycle

This notice serves as Addendum No. 2 to the above referenced project. This addendum addresses additional items of concern since the release of Addendum No 1.

## CLARIFICATIONS

1. The Bid Due Date has been changed from Tuesday April 6, 2010 at 2:00 PM to Thursday April 8, 2010 at 3:00.
2. Clarification: All cap stones on structure shall have a 1" overhang on all sides.
3. Clarification: Pavers – the ground under the sand bed shall be compacted and have a 2" layer of crushed stone. Crushed stone shall be compacted to make a flat level surface. Contractor to use natural redwood for the edging material. Edging shall be secured in place. Joints between pavers shall be filled in with coarse sand. The finish floor of paver pad shall be flush with the top of curb.